HASSAN DIVISION.

Dated 1st March 1911.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan Division, up to 15th March 1911, for restoring Anugavalli Tank, Registered No. 523, Hassan Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1912.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Hassan, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Anugavalli Tank, Registered No. 523, Hassan Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Northern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Bund R. L. 56·60.

		Per.	*Quantity.*
Earthwork, raising bund		C. yd.	18,167
Turfing		S. yd.	13,373
Rough stone work, new		C. yd.	2,917
Repairing and fixing grade stones		Each	40
Do	Visa Via stones	Each	40
Do	B. M. stones	Each	2
Do	Gauge stone	Each	3
Do	Register number stone	Each	1
Clearing jungle		Lump sum.	
Gravel backing		C. yd.	809

Right weir 160 *feet long R. L.* 50·00.

Earthwork excavating and using to T. bank and forming ramp in front	C. yd.	820
Brick in surki mortar	C. ft.	1,448
Burnt stone slabs, 6" thick	S. ft.	474
Plastering with surki mortar	Sqr.	2·68
Rough stone work, new	C. yd.	418
Do old	do	54
Clearing draft hard soil	do	570

Left weir 100 *feet long R. L.* 50·00.

Earthwork excavating foundation and forming ramp in front	C. yd.	1340
Brick in surki mortar	C. ft.	1,915
Burnt stone slabs	S. ft.	327
Plastering with surki mortar	Sqr.	4·11
Rough stonework, new	C. yd.	284
Clearing draft ordinary soil	do	250

Sluice No. 3.

Examining and constructing front and rear cisterns and repairing tunnels, etc.	Lump sum.

V. AIYASWAMI IYER,
Executive Engineer.